

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-145-21,297.0000

LEASE NAME Ellis

WELL NUMBER #9-8

3630 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 9 TWP. 20S RGE. 19 (KK) or (W)

COUNTY Pawnee

Date Well Completed 8/30/89

Plugging Commenced 12/27/89

Plugging Completed 11:30A.M. 12/27/89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kodiak Petroleum, Inc.

ADDRESS 44 Inverness Drive East, Suite B, Bldg D

Englewood CO 80112  
PHONE#(303)790-7550 OPERATORS LICENSE NO. 9971

Character of Well Non-commercial gas well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 26, 1989 (date)

by Mr. Steve Durant, Dodge City, witnessed plugging (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Chase Depth to Top 2319 Bottom 2398 T.D. 2500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Krider	gas & water	2319	2351	8 5/8"	464.5'	0
Winfield	gas & water	2368	2398	4 1/2"	2499'	1867'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sand to 2275', 4 sx cmt; shot off casing at 1867'; pull 46 jts; mixed and pumped 300# hulls, 10 sx gel, 50 sx 60/40 Posmix w/ 6% gel, SI @200 psig. Released 1-8 5/8" wooden plug. Mixed and pumped 100# hulls, 10 sx gel, 150 sx 60/40 Posmix w/6% gel, min. press 800 psig. SI @ 400 psig.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cement Company License No. \_\_\_\_\_

Address PO Box 31 Russell KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kodiak Petroleum, Inc.

STATE OF Colorado COUNTY OF Arapahoe, ss.

Kent A. Johnson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. help me God.

MAR 19 1990

(Signature) [Signature]

CONSERVATION DIVISION  
Wichita, Kansas

(Address) 44 Inverness Dr. E, Suite B, Bldg D

Englewood CO 80112

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 90

Judith C. Pennington  
Notary Public

My Commission Expires: April 19, 1993