

APR 22 1974
CONSERVATION DIVISION
Wichita, Kansas

Form CP-1

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Pawnee County, Sec. 9 Twp. 20 Rge. 19 (E) (W) X
Location as "NE/CNW/SW" or footage from lines SW NE SE
Lease Owner National Cooperative Refining Assn.
Lease Name Matoush Well No. #2
Office Address Box 6 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4-13-74 19
Plugging completed 4-16-74 19
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4230' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4230'	3246.73'
				8 5/8"	132'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 4150'. Mixed and ran 5 sacks cement thru dump bailer.
Squeezed hole with 2' sacks hells - 22 sacks gel - 1 sack hull, 70 sacks cement and 8 sacks gel.
Released plug and displaced with 50 sacks cement.

Name of Plugging Contractor Southwest Casing Pulling Co. (If additional description is necessary, use BACK of this sheet)
Address Box 364 Great Bend, Kansas


STATE OF Kansas COUNTY OF Barton
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364 Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 19 day of April 1974

My commission expires 24 October 1976
Sidney D. Miller
Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company. M. B. ARMER
Farm. Matoush

No. 2

SEC. 9 T. 20 R. 19W
SW NE SE

Total Depth. 4230

Comm. 10-10-54

Comp. 10-22-54


Shot or Traced.

Contractor Armer, Inc.

Issued. 1-15-55

County Pawnee

KANSAS



Elevation. 2249 KB

Production. 298 bbls.

CASING:

8 5/8 132'
5 1/2 4230'

Figures Indicate Bottom of Formations.

shale & shells	225
sand	310
shale & shells	400
sand	430
shale & shells	840
Dakota sand	960
shale & shells	1210
red bed	1395
anhydrite	1665
shale & shells	1940
shale & lime	2615
shale & shells	2725
shale & lime	3110
shale & shells	3230
shale	3315
shale & lime	3500
lime	3650
lime & shale	3729
lime	4055
lime & shale	4170
lime	4200
sandy shale & lime	4230
Total Depth	

TOPS: (KB Meas.)

Heebner	3674
Lansing-KC	3721
Shaley conglomerate	4150
Conglomerate sand	4192

RECEIVED
STATE CORPORATION COMMISSION

APR 8 - 1974

CONSERVATION DIVISION
Wichita, Kansas