


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 10 Twp. 20 Rge. (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines C W/2 NW SE/4
Lease Owner Armer, Inc.
Lease Name Josefiak Well No. 1
Office Address 710 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed May 25, 19 55
Application for plugging filed " " 19 " "
Application for plugging approved " " 19 " "
Plugging commenced " " 19 " "
Plugging completed " " 19 " "
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner
Producing formation Depth to top Bottom Total Depth of Well 4288 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	135'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud, pumped plug and 125 sacks cement, filling hole and surface pipe from 375 ft. to base of cellar with cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Armer, Inc.
Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
L. C. Sponenberg (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. C. Sponenberg*
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 55

My commission expires February 13, 1956.

Rose Turley
RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

PLUGGING
PAI SEC 10 T 20 R 19W
CSDI 222/22 JUN 30

JUN 1 - 1955
CONSERVATION DIVISION
Wichita, Kan.

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15.145.00949.0000

COMPANY Armer, Inc.

SEC. 10 T. 20 R. 19W
 LOC. C W/2 NW SE

FARM Josefiak NO. 1

TOTAL DEPTH 4288

COUNTY Pawnee


COMM. 5/11/55

COMP. 5/25/55

KANSAS

SHOT OR TREATED

CONTRACTOR Armer, Inc.



ISSUED

CASING

20	10	
15	8	135!
12	6	
13	5	

ELEVATION 2216 K.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Red rock & Shale	100
Shale & Shells	135
Sandy Shale, Red Bed & Shells	1050
Shale & Shells	1352
Anhydrite	1385
Shale, Red Bed & Shells	1400
Shale & Shells	2165
Lime & Shale	3765
Lime	4060
Lime & Shale	4196
Shale & Sand	4207
Lime & Shale	4217
Shale	4260
Shale & Chert	4283
Chert	4288

FORMATION TOPS

HEEBNER	3677
TORONTO	3694
LANSING	3726
BASE KANSAS CITY	4036
CONGLOMERATE SAND	4191
MISSISSIPPIAN	4278

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

RECEIVED
 STATE CORPORATION COMMISSION

ARMER, INC.

JUN 1 - 1955

CONSERVATION DIVISION
 Wichita, Kansas

By *C. P. Sprouling*

STATE OF KANSAS }
 } SS:
 COUNTY OF SEDGWICK }

Subscribed and sworn to before me, a notary public, in and for said County and State this 27th day of May, 1955.

W. J. Furey
 Notary Public

My Commission Expires February 13, 1956.

PLUGGING
 FILE SEC 10 T 20 R 19W
 BOOK PAGE 122 LINE 30