

15.145.20014.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Misco-United Supply, Inc.
Complete Address 257 N. Broadway Wichita, Kansas 67202
Lease Name Boyd Well No. 1
Location NW SW SE Sec. 25 Twp. 20 Rge. (E) (W) 19
County Pawnee Total Depth 4175'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas 67530 License No. 399
Operation Completed: Hour 10:45 A Day 13 Month 4 Year 1973

The above well was plugged as follows:

Total Depth 4175' 8 5/8 csg set at 385' cwc 165 sk.
4 1/2 csg set at 4173' cw 135 sk cmt. Perf. (4119-4126)
Filled 4 1/2 csg W/sd (4100-4175) Dumped 4 sk cmt W/dump bailer. (4065-4100)
Cutoff and recovered 2925' of 4 1/2 csg.
Pumped down 8 5/8 csg with 17 sk gel & water W/300 lbs hulls, -released plug &
displaced with 8 sk gel & water, -capped with 20 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Messing
Well Plugging Supervisor

INVOICED

DATE 4/16/73
INV. NO. 7240-U