

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 16 1973

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Misco-United Supply, Inc.

Complete Address 257 N. Broadway Wichita, Kansas 67202

Lease Name Boyd 'A' Well No. 2

Location SE SW SE Sec. 25 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4135'

Abandoned Oil Well Gas Well Input Well SWD Well XXX D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 9:45 A Day 13 Month 4 Year 1973

The above well was plugged as follows:

Total Depth 4135' 8 5/8 csg set at 363' cwc 200 sk.4 1/2 csg set at 4135' cw 120 sk cmt.4 1/2 csg perf. (4079 1/2 - 4095 1/2)4 1/2 csg squeezed at 1262' W/125 cu. ft. cem. & perf. (807-874)Filled 4 1/2 csg with sand (4050-4135) Dumped 4 sk cmt W/dump bailer. (4015-4050)~~Reamed~~ Cutoff and recovered 500' of 4 1/2 csg.Pumped down 8 5/8 csg with 15 sk gel & water W/300 lbs hulls, released plug &pumped 120 sk 50-50 poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Bro F. Murray
Well Plugging Supervisor

INVOICED

DATE 4/16/73INV. NO. 4241-W