

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name J. A. Allison

Complete Address 1415 Vickers KSB&T Bldg., Wichita, Kansas 67202

Lease Name Boyd Well No. 4

Location C W/2 SE SE Sec. 25 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4070'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Ralph Comstock

Address Stafford, Kansas 67578 License No. 490

Operation Completed: Hour 11:30 A Day 24 Month 7 Year 1972

The above well was plugged as follows:

Total Depth 4070' 8 5/8 csg set at 358' cwc 185 sk. Cmt. Mat. 50-50 poz cmt 6% gel.

5 1/2 csg set at 4069' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (4030-4070) dumped 5 sk cmt W/dump bailer. (3995-4030)

Cutoff and recovered 2120' of 5 1/2 csg.

Pumped down 8 5/8 csg with 14 sk gel & water W/500 lbs hulls 85 sk cmt, 6 sk

gel & water & 15 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. F. Massey
Well Plugging Supervisor

DATE 7-28-72

INV. NO. 6064-112