

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-145-20917

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Plano Petroleum Co.

Complete Address ¹¹³⁰ East Plano Parkway #100 Box 1386 Plano Texas 75074

Lease Name Snodgrass Well No. 1

Location SW-SW-SE¹/₄ Sec. 1 Twp. 20 Rge. 20W (East)(West)

County Pawnee Total Depth 4410'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling Co.

Address Box 1418 License No. _____

Operation Completed: Hour: 7:15 PM Day: 8 Month: December Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 534' of 8 5/8" surface casing cement circulated with
275 Sby of cement 2% Jell 3% CC. The anhydrate was at 1470'
The Debata was at 1200'. 1st plug with hole full of heavy
mud was at 1425' with 70 Sby of cement. 2nd plug push
rubber plug to 510' and pumped 35 Sby of cement on top of
it. 3rd plug on solid bridge 40' to 0' with 10 Sby of cement.
They pumped 5 Sby of cement in each the rat hole + the
mouse hole. The plugging was accomplished by
Applied Cementers.

RECEIVED

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luthie
Conservation Division Agent

INVOICED

DATE 1-21-82

INV. NO. 9085-W CONSERVATION DIVISION
Wichita, Kansas

12-11-81