

15.145.30006.0000

Form CP-3  
Rev. 6-26-62

*R* KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

MAR 23 1965  
3-23-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dorset Co  
Complete Address: 610 National Bank Tulsa, Okla  
Lease Name Russell Well No. 1  
Location NE NE NW Sec. 1 Twp. 20 Rge. (E) (W) 20  
County Pawnee Total Depth 4390  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A x  
Other well as hereafter indicated:       
Plugging Contractor: Garvey Drg Co  
Address: Great Bend, Kans License No.       
Operation Completed: Hour 11AM Day 18 Month 3 Year 65

The Above well was plugged as follows:

8 5/8" 483' circulated with cement 325 sax'

Circulated hole with heavy mud, set plug at 480', displaced 20 sax  
cement through drill pipe, heavy mud to 240', set plug and displaced  
20 sax cement through drill pipe, heavy mud to 40', set plug, hulls and  
filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edwin Petty  
Well Plugging Supervisor

DATE 3/23/65  
INV. NO. 862-W