

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company, Inc.

Complete Address P. O. Box 349 Russell, Kansas 67665

Lease Name Harms Well No. 4

Location G NE NW Sec. 23 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4300'

Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 11 A Day 25 Month 5 Year 1971

The above well was plugged as follows:

Total Depth 4300' 8 5/8 csg set at 370' cwc

4 1/2 csg set at 4299' cw 125 sk cmt.

4 1/2 csg PBTD 4268' with top perf. (4193)

Filled 4 1/2 csg W/sd (4175-4268) Dumped 4 sk cmt W/dump bailer. (4140-4175)

Recovered 2720' of 4 1/2 Csg.

Pumped down 8 5/8 csg with 20 sk gel W/3 sk hulls, release plug and pumped 120 sk

50-50 poz W/4% added gel. Max. pres. 1000 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Massey  
Well Plugging Supervisor

DATE 6/1/71

INV. NO. 3771-44