

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 12 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Mull Drilling Company, Inc.,

Complete Address: 1625 Wichita Plaza Wichita, Kansas

Lease Name Ideker Well No. 1

Location C NW SW Sec. 23 Twp. 20 Rge. 19 (E) (W) X

County Pawnee Total Depth 4329'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Forbes Casing Pulling, Inc.,

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 4 P Day 9 Month 6 Year 1967

The Above well was plugged as follows:

Total Depth 4329' 8 5/8 csg set at 330' cwc 225 sc.

4 1/2 csg set at 4328' cw 150 sc cement.

PB to 4250' with top perf. at 4222'.

Filled with sand to 4200' and dumped 3 sc cement with dump bailer.

Recov. 3200' of 4 1/2 csg.

Mud to 325'. Set plug and dumped 5 sc cement with dump bailer. Top of cement 310'.

Bailed dry, set 25 sc cement plug (310-235 ).

Mud to 40' set rock bridge and 10 sc cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rud. Massey  
Well Plugging Supervisor

DATE 6/12/67

INV. NO. 5366-u