

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 22 1978

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 145 - 00412.0000 (of this well)

Operator's Full Name Mull Drilling Co., Inc.

Complete Address 415 Page Ct. - 220 W. Douglas, Wichita, Kansas 67202

Lease Name Anna Harms Well No. 1

Location NW SE NW Sec. 23 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4305'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas License No. 670

Operation Completed: Hour 2:30 P Day 21 Month 3 Year 1978

The above well was plugged as follows:

Total Depth 4305' 8 5/8 csg set 435' cwc 250 sk.

4 1/2 csg set 4305' cw 140 sk cem. Top perf. (4218')

Filled 4 1/2 csg W/sd (4305'-4200') dumped 4 sk cem W/dump bailer. (4200'-4165')

Cutoff & recovered 800' of 4 1/2 csg.

Halliburton Cementing mixed & pumped down 8 5/8 csg with 25 sk gel & water W/100 lbs hulls, released 8 5/8 cementing plug & pumped 140 sk 50-50 poz 2% & shutin.

FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey  
Well Plugging Supervisor

DATE 3-23-78  
INV. NO. 6985-6