

 KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

2 0 0 0

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Wichita, Ks.

Lease Name Holman Well No. 1

Location NE SE Sec. 22 Twp. 20 Rge. 19 (E) (W) X

County Pawnee Total Depth 4315

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Plg. Inc.

Address: Great Bend, Ks. Box 221 License No. 49

Operation Completed: Hour 1 P Day 24 Month 2 Year 1968

The Above well was plugged as follows:

Total Depth 4315' 8 5/8 csg set at 365' cwc 200 sc.

4 1/2 csg set at 4314' cw 125 sc cement.

4 1/2 PBTD 4284'/ Top perf. at 4234'

Filled with sand to 4200' and dumped 4 sc cement with dump bailer.

Recov. 2400' of 5 1/2 csg.

Pumped thru 8 5/8 plg container with 25 sc gel W/5 hulls, followed with 110 sc cem,

5 sc gel, plg and 10 sc cement to surface.

Cement: (0-50) gel (50-300) cement (300-660) gel (660-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bio F. J. Massey  
Well Plugging Supervisor

DATE 2/26/68

INV. NO. 7323-11