

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
JUL 31 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Association

Complete Address Box #6 Great Bend, Kansas 67530

Lease Name Eckert Well No. 2

Location NW SW NW Sec. 18 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4330'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling

Address Box 1082, Great Bend, Kansas License No. 623

Operation Completed: Hour 1 P. Day 29 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 4330' 10 3/4 csg set at 457' cwc 300 sk.

7" csg set at 4323' cw 100 sk com. & perf. (4231-4238)

Filled 5 7/8" csg with sand to 4000' & dumped 6 sk cem W/dump bailer.

Pumped down 10 3/4 csg with 25 sk gel & water -released 10 3/4 plug & pumped 60 sk

cem. -displaced with 10 sk gel & water & capped with 25 sk cem W/100 lbs ball.

I hereby certify that the above well was plugged as herein stated.

Signed: Ben Z. Massey
Well Plugging Supervisor

INVOICED

DATE 7/31/74

INV. NO. 9635-W