

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED
JUL 31 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name National Cooperative Refinery Association

Complete Address Box #6, Great Bend, Kansas 67530

Lease Name Eckert Well No. 3

Location NW NE NW Sec. 18 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4331'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling

Address Box 1082, Great Bend, Kansas License No. 623

Operation Completed: Hour 11 P Day 29 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 4331' 8 5/8 csg set at 455' cwc 300 sk.

5 1/2 csg set at 4330' cw 100 sk cmt. & perf. (4224-4282)

Filled 5 1/2 csg with sand to 4100' -dumped 5 sk com W/dump bailer.

Recovered 2300' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs hulls -50 sk com, 8 sk gel

& water & capped with 20 sk com.

I hereby certify that the above well was plugged as herein stated.

Signed: Russ Casing Pulling
Well Plugging Supervisor

INVOICED

DATE 7/31/74

INV. NO. 9636-W