

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name National Cooperative Refinery Association

Complete Address P. O. Box # 6 Great Bend, Kansas 67530

Lease Name Eckert Well No. 1

Location NW NW NW Sec. 18 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4300'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1:45 P Day 29 Month 12 Year 1973

The above well was plugged as follows:

Total Depth 4300' 8 5/8 csg set at 343' cwc 200 sk.

5 1/2 csg set at 4299' cw 100 sk cmt.

5 1/2 csg PBTD 4270' with top perf. (4223)

Filled 5 1/2 csg W/sd (4200-4270) dumped 4 sk cmt W/dump bailer. (4170-4200)

Cutoff and recovered 2800' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -released 8 5/8 plug

and pumped 70 sk cement -displaced with 5 sk gel & water & capped with 20 sk cem.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Maisey
Well Plugging Supervisor

INVOICED

DATE 1/4/74

INV. NO. 8365-W