

ST

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Building, Wichita, Kansas

Lease Name Batchman "A" Well No. 2

Location C SW NE Sec. 7 Twp. 20 Rge. 20 (E) (W) XX

County Pawnee Total Depth 4379

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XXX

Other well as hereafter indicated:     

Plugging Contractor: Go. Tools

Address:      License No.     

Operation Completed: Hour 10:45A Day 28 Month 12 Year 1968

The Above well was plugged as follows:

RTD 4379' 8 5/8 csg set at 269' cwc Cmt. Mat. 100 sk Comm cmt. W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing  
Well Plugging Supervisor

INVOICED

DATE 12-30-68

INV. NO. 9122-W