

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company & Southwest Petro-Chem

Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Batchman "A" Well No. 3

Location C NW NE Sec. 7 Twp. 20 Rge. (E) (W) 20

County Pawnee Total Depth 4372'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 8:30 A Day 13 Month 3 Year 1972

The above well was plugged as follows:

RTD 4372' 8 5/8 csg set at 265' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Low A. Wassell*
Well Plugging Supervisor

INVOICED

DATE 3/17/72
INV. NO. 5373-W