

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas 67202

Lease Name Bartonek Well No. 1 -V

Location SE NW SW Sec. 20 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4325'

Abandoned Oil Well XX Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 10 P Day 20 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 4325' 8 5/8 csg set at 451' cwc 250' sk.

5 1/2 csg set at 4320' cw 150' sk cmt.

5 1/2 csg PBD 4291' with perf. (4185')

5 1/2 csg packer left in hole at 3900' () dumped 5 sk cmt W/dump bailer. ()

Filled 5 1/2 csg W/sd (3850-3900) Dumped 5 sk cmt W/dump bailer. (3815-3850)

Pumped 8 s/8 csg with 18 sk gel & water W/300 lbs hulls, released 8 5/8 plug and

pumped 70 sk cmt, -7 sk gel & water & capped with 20 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Murray
Well Plugging Supervisor

INVOICED
DATE 3-23-72
INV. NO. 5386-62