

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 17 Twp 20S Rge. (E) 19 (W)  
Location as "NE/CNW/SW" or footage from lines C SE NW  
Lease Owner Rains & Williamson Oil Co.  
Lease Name Drake Well No. 1  
Office Address 1425 Wichita Plaza Bldg.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-10 19 66  
Application for plugging filed 5-9 19 66  
Application for plugging approved 5-9 19 66  
Plugging commenced 5-9 19 66  
Plugging completed 5-10 19 66  
Reason for abandonment of well or producing formation no oil or gas found in commercial quantities.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4362 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	391.46	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed bottom plug to 600'. Spot 30 Sx. cement. Mud back to 380' and spot 20 sx. Pushed plug 20'. Mud back to 40' set solid bridge and capped with 10 sx.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 12 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 1425 Wichita Plaza Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Wilson Rains, Partner (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
Wilson Rains  
1425 Wichita Plaza Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 66

My commission expires 3-3-70  
Mary J. Brown  
Mary J. Brown Notary Public.

## ROTARY DRILLING LOG

OPERATOR: Rains & Williamson Oil Co. #1 Drake C SE NW Sec. 17-20S-19W Pawnee County, Kansas	CONTRACTOR: Rains & Williamson Oil Co. COMMENCED: 4-30-66 COMPLETED: 5-10-66 REMARKS: Set 391.46' of 8-5/8" surface pipe with 225 sacks of GL3.
--	--

## FORMATIONS

Shale & Red Bed	780'
Sand	935'
Red Bed & Shale	1215'
Shale & Red Bed	1367'
Anhydrite	1394'
Shale	1620'
Shale & Shells	2100'
Lime & Shale	2430'
Lime	2665'
Lime & Shale	3255'
Lime	4060'
Lime & Shale	4100'
Lime	4212'
Lime & Sand Shale	4260'
Lime	4362'
Rotary Total Depth (D & A)	4362'

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 11th day of May, 1966.

My Commission Expires: 3-3-70

*Mary J. Brown*  
Mary J. Brown Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

MAY 12 1966

CONSERVATION DIVISION  
TOPEKA, KANSAS