

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-21,260.0000

LEASE NAME S.O.P. Sturgeon

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 16 TWP. 20S RGE. 19 ~~REXX(W)~~

COUNTY Pawnee

Date Well Completed 6-8-87

Plugging Commenced 6-8-87

Plugging Completed 6-8-87

LEASE OPERATOR Lawbanco Drilling, Inc.

ADDRESS P. O. Box 289, Natoma, KS 67651

PHONE#(913) 885-4557 OPERATORS LICENSE NO. 5900

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District #1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	388'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4350' - 1350'

60 sks cement @ 1350'

10 sks cement @ 40'

50 sks cement @ 750'

15 sks in Rathole

40 sks cement @ 390'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 87

Glenda R. Tiffin
Notary Public

Expires: February 6, 1988



Rec'd
JUN 17 1987
KCC

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Lawbanco Drilling, Inc.
P. O. Box 289
Natoma, KS 67651

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: S.O.P. Sturgeon WELL #1

LOCATION: NE NE SE
Section 16-20S-19W
Pawnee County, Kansas

LOGGERS TOTAL DEPTH: 4352'

ROTARY TOTAL DEPTH: 4350'

COMMENCED: 6/2/87

CASING: 8-5/8" @ 388' w/185 sks cement

ELEVATION: 2245' K.B.

COMPLETED: 6/8/87

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Topsoil & Sand	37'	Shale	1366'
Shale	254'	Anhydrite	1440'
Dakota	335'	Shale	2220'
Redbed	390'	Shale & Lime	2560'
Redbed & Shale	654'	Lime & Shale	3305'
Shale	839'	Lime	3993'
Sand	1026'	Lime & Shale (R.T.D.)	4350'

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on June 17, 1987.

My commission expires: February 6, 1988.

Rec'd
JUN 17 1987
KCC


Glenda R. Tiffin, Notary Public

