

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 15 Twp. 20 Rge. 19 (E) W (W)

Location as "NE/CNW&SWK" or footage from lines NW/4 - NW/4 - SE/4

Lease Owner Toklan Prod. Co.

Lease Name Winkler Well No. 1

Office Address 1202 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-11 1953

Application for plugging filed 8-11 1953

Application for plugging approved 8-11 1953

Plugging commenced 8-15 1953

Plugging completed 8-15 1953

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4569 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	308	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled Hole with heavy mud to 300' - Pushed wooden plug and Hulls to 300' - Run 20 sax cement through drill pipe - Filled hole with mud to 40' - Pushed wooden plug to 40' and anchor with wire - run 10 sax cement filling hole to cellar floor

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Salina Drilling Corp.

Address 801 N. 10th St. Salina, Kansas.

STATE OF Kansas, COUNTY OF Saline, ss. Elmer Rider (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmer Rider Elmer Rider

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1953

Laurence J. Wickersham Notary Public.

My commission expires April 19, 1954

24-2675-5 2-52-20M

PLUGGING
FILE SEC 15 T 20 R 19 W
BOOK PAGE 122 LINE 8

VED
ON COMMISSION
AUG 24 1953
8-24-53
ON DIVISION

ROTARY DRILLER'S LOG

Winkler #1

Elevation: 2235 D F 2238 RB

NW/4 NW/4 SE/4 Sec. 15, Twp 20,
R 19W, Pawnee County, Kansas.

"Casing Record"
308' 8 5/8" - - - - - 200 sax cement

Operator: Tpklan Production Co.
Tulsa, Oklahoma.

Contractor: Salina Drilling Corporation, Inc.
Box #566, Salina, Kansas.

Well Commenced: 7-27-53

Geologist: Douglas H. McGinness
Union National Bank Building
Wichita, Kansas.

Well Completed: 8-15-53

Surface Soil	5	Lime Broken	2855
Clay	25	Shale	2960
Shale & Lime Shells	110	Lime & Shale	3080
Shale	190	Broken Lime	3360
Shale & Shells	780	Shale & Shells	3460
Red Bed	815	Shale & Lime	3555
Sand & Shale	1100	Broken Lime	3625
Shale, Shells, & Red Bed	1397	Lime	3644
Anhydrite	1425	Shale & Shells	3666
Shale & Shells	1680	Hubner	3670
Shale & Lime Shells	1955	Lime	3926
Shale & Shells	2150	Cherty Lime	3946
Lime	2155	Lime	4375
Lime & Shale Broken	2285	Lime & Chert	4425
Shale & Broken Lime	2380	Mississippi Lime	4475
Broken Lime	2480	Lime	4498
Lime	2624	Shale	4525
Lime Broken	2675	Lime	4544
Lime	2815	Arbuckle Lime	4569

GEOLOGISTS TOPS

Hubner	3573	Viola	4509
Lansing	3803	Simpson	4535
Sand	4270	Arbuckle	4544
Chert Conglomerate	4309		
Mississippi Chert	4393		
Kinderhook	4497	Rotary Total Depth	4569

The above Rotary Drillers Log is complete and correct to the best of my knowledge.

SALINA DRILLING CORPORATION, INC.

Loren S. Hallam
President

PLUGGING
DLK SEC 15 Twp 20 R 19W
BOOK PAGE 122 LINE 8

RECEIVED
2002
OPERATION DIVISION
Wichita, Kansas