


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 25 Twp. 20 Rge. (E) 19 (W)
Location as "NE/CNWSW" or footage from lines NE SW SE
Lease Owner J. A. Allison
Lease Name Boyd Well No. 3
Office Address 1415 Wichita Plaza Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed February 2, 1970 19
Application for plugging filed July 14, 1972 19
Application for plugging approved July 17, 1972 19
Plugging commenced July 20, 1972 19
Plugging completed July 24, 1972 19
Reason for abandonment of well or producing formation unprofitable production

If a producing well is abandoned, date of last production October 31, 1971
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Cherokee Depth to top 4069 Bottom 4087 Total Depth of Well 4087 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Cherokee	oil	4069	4087	8 5/8	@ 368	
				4 1/2	4082	2300

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dig out cellar & deadman holes - set unit - rig up.
Sand back to 4030 - dump 4 sx cement - lead hole with
water - pull slips - work pipe 22" - shoot @ 2396 & 2300.
Pull 73 jts 4 1/2" pipe - total 2300' - tear down.
Pumped 5 sx hulls, 20 sx gel & 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1972
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock
Address 320 N. Park, Stafford, Ks.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
J. A. ALLISON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Allison
1415 Wichita Plaza Bldg., Wichita, Ks.
(Address)

Subscribed and sworn to before me this 30th day of August, 1972



Frances O. Erhard
Frances O. Erhard Notary Public.

B & B DRILLING, INC.

548 Petroleum Building

Wichita, Kansas 67202

February 4, 1970

15.145.20141.0000

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

Re: Boyd #3
NE SW SE Section 25-20S-19W
Pawnee County, Kansas

OPERATOR: J. A. Allison
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: January 23, 1970
COMPLETED: February 2, 1970
TOTAL DEPTH: 4087'

Set 8 5/8" @ 368 w/200 sx

0	368	Surface & Clay	
368	458	Shale	
458	676	Shale & Red Bed	
676	801	Sand	
801	1245	Shale	
1245	1291	Anhydrite	
1291	1600	Shale	
1600	1950	Shale & Shells	
1950	2165	Shale	
2165	2339	Shale & Lime Streaks	
2339	2418	Lime & Shale	
2418	2620	Lime	
2620	2724	Lime & Shale	
2724	3194	Lime & Shale	
3194	3640	Lime & Shale	
3640	3749	Lime & Shale	
3785	4058	Lime	
4058	4070	Core #1	
4070	4085	Core #2	
4085	4087	Total Depth	Ran 4 1/2" @ 4089'

We certify the above and foregoing to be true and correct copy of the log on the #3 Boyd, located in Pawnee County, Kansas

Bill Baker President

Alma A. Neess Notary Public
Subscribed and sworn to before me this 4th
of February, 1970. My commission expires
May 31, 1970