


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pawnee County, Sec. 25 Twp. 20 Rge. 19 (E) (W) X
Location as "NE/CNW/SE" or footage from lines NW SW SE
Lease Owner Misco United Supply Inc.
Lease Name Boyd Well No. #1
Office Address 257 N. Broadway Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 2-22-73 19
Plugging commenced 4-6-73 19
Plugging completed 4-13-73 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4175' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	4173'	2940.82'
				8 5/8"	385'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 4100'. Mixed and ran 4 sacks cement thru dump bailer.
Squeeze hole with 3 sacks hulls and 17 sacks gel. Released plug 100 sacks cement and 8 sacks gel. Displaced with 20 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec
Box 364 Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 16 day of April, 1973

My commission expires 22 October 1976

Sidney S. Miller
Notary Public.

STENCILLED

NOV 18 1967

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

ORIGINAL

15.145.20014.0000

COMPANY W. F. Newton

SEC. 25 T. 20 R. 11W
LOC. NW SW SE

FARM Boyd

NO. 1

TOTAL DEPTH 4175'

COUNTY Payne


COMM. Aug. 14, 1967 COMP. Aug. 26, 1967

KANSAS

SHOT OR TREATED

CONTRACTOR Woodman & Iannitti Drilling Co.

ISSUED 11-18-67



CASINO

20 10
15 8 5/8 @ 385' cem w/ 165x
12 6
13 5
4" 4173' cem w/ 135 SX
FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION 2184' KB

PRODUCTION 61 BOPD PLUS 50% W,
Cherokee 4119-26

40	Post Rock	TOPS: SMP
110	Clay & Shale	Heebner 3608
230	Red Bed & Clay	Toronto 3627
285	Sand	Lansing Kansas City 3660
387	Clay & Shale	Base Kansas City 3958
560	Blue Shale	Cherokee 4086
710	Red Bed	Arbuckle 4155
925	Sand	
1200	Red Bed	
1294	Red Bed	
1324	Anhy	
1410	Shale & Shells	
2010	Shale & Shells	
2100	Lime & Shale	
2275	Lime	
2405	Lime	
2495	Lime	
2615	Lime	
2705	Lime	
2845	Lime	
28.5	Lime	
3115	Lime & Shale	
3200	Lime	
3335	Lime	
3400	Lime	
3575	Lime	
3675	Lime	
3750	Lime	
3800	Lime	
3855	Lime	
3920	Lime	
3962	Lime	
4027	Lime	
4095	Lime	
4126	Lime	
4138	Lime	
4173	Chert & Lime	
4175	Total Depth	

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1973
CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and correct copy of the driller's log and the geological tops to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman