


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Pawnee County. Sec. 25 Twp. 20 Rge. 19 W (E) (W)

Location as "NE/CNWxSWx" or footage from lines NE NE SW

Lease Owner Raymond Oil Company, Inc.

Lease Name BOYD ESTATE Well No. 1

Office Address 410 Fourth National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 12, 1962 19

Application for plugging filed (Verbal) October 12, 1962 19

Application for plugging approved (Verbal) October 12, 1962 19

Plugging commenced October 12, 1962 19

Plugging completed October 12, 1962 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. W. L. LaKamp, Stafford, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4325 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	407'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill hole to 370' with mud.  
Set plug @370', mix 25 Sxs. cement through  
drill pipe.  
Fill hole to 35 ft. with mud. Set plug, 10 Sxs. cement.  
2 Sxs. cement in rat hole

RECEIVED  
STATE CORPORATION COMMISSION

OCT 23 1962

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Raymond Oil Company, Inc.

Address 410 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Patrick R. Raymond (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
410 Fourth National Bank Building, Wichita  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 19 62

My commission expires July 9, 1966

[Signature]  
Notary Public



15.145.00503.0000

RAYMOND OIL COMPANY, INC.  
No. 1 BOYD ESTATE  
NE NE SW 25-20-19W  
Pawnee County, Kansas

ELEVATION: 2179 KB  
2177 DF

Contractor: Raymond Oil Company, Inc. - Rig #3  
Commenced: September 30, 1962  
Completed: October 12, 1962  
Casing Record:  
8-5/8" @407' w/250 Sx.

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Postrock and Clay	50
Clay and Sand	100
Shale, sand and Shells	280
Shale and Shells	407
Shale and Sandstone	547
Redbed	720
Sand	860
Shale	1210
Shale and Shells	1292
Anhydrite	1320
Shale and Shells	1760
Shale with Lime Streaks	2100
Shale and Lime	2385
Lime	2615
Lime and Shale	3509
Lime	4145
Lime and Shale	4180
Lime	4208
Lime and Chert	4267
Lime, Chert and Shale	4296
Lime and Shale	4325 TD

TOPS


Heebner	3620
Toronto	3642
Lansing	3672
Base Kansas City	3976
Cherokee Shale	4106
Conglomerate	4151
Arbuckle	4223
Rotary Total Depth	4328 Schlumberger
Rotary Total Depth	4325

RECEIVED  
STATE CORPORATION COMMISSION


OCT 23 1962

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the above to be true and correct to the best of my knowledge.

  
Patrick R. Raymond, Vice President

Subscribed and sworn to before me this 22nd day of October, 1962.

  
Notary Public

My commission expires:  
July 9, 1966