

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Pawnee County. Sec. 26 Twp. 20 Rge. 19 (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Musgrove Petroleum Corporation
Lease Name EDWARDS Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed July 26, 1955
Application for plugging filed verbally July 26, 1955
Application for plugging approved verbally July 26, 1955
Plugging commenced July 26, 1955
Plugging completed July 26, 1955
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Box 207, Great Bend, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4500' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	402.67'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/mud to 300'
1st plug set at 300' w/25 sx cement through drill pipe
Filled hole w/mud to 35'
2nd plug set at 35' w/10 sx cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation
Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling Secretary-Treasurer
518 Petroleum Bldg.,
Wichita, Kansas.

SUBSCRIBED AND SWORN to before me this 29th day of July, 1955

Leah Faye Heike
Leah Faye Heike
Notary Public.

My commission expires June 16, 1959

RECEIVED
STATE CORPORATION COMMISSION
AUG 2 X 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 26 T 20 R 19 W
BOOK PAGE 138 LINE 17

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: EDWARDS #1
 LOCATION: NE NE NE Section 26-20-19
 Pawnee County, Kansas
 COMMENCED: July 12, 1955
 COMPLETED: July 26, 1955

0	140	Surface clay & shells
140	739	Shale & shells
739	895	Sand
895	950	Shale & Sand
950	1329	Shale & shells
1329	1360	Anhydrite
1360	2085	Shale & shells
2085	2283	Lime & shale
2283	2425	Lime
2425	2535	Lime & shale
2535	2655	Lime
2655	3506	Lime & shale
3506	4024	Lime
4024	4233	Lime & shale
4233	4255	Sand, chert, lime & shale
4255	4324	Cherty lime & shale
4324	4368	Lime & chert
4368	4386	Lime, chert & shale
4386	4402	Cherty lime, shale & sand
4402	4435	Sand
4435	4500	Lime
	4500	Rotary Total Depth

Set 8-5/8" surface at 402.67' with 250 sx cement, 2% calcium chloride.

Dry and Abandoned

ELEVATION:	2207' K. B.	Sandy Conglomerate	4221'	(-2015)
SCHLUMBERGER TOPS:		Mississippi Chert	4315'	(-2108)
Heebner	3700' (-1493)	Mississippi Lime	4371'	(-2164)
Toronto	3718' (-1511)	Kinderhook Shale	4400'	(-2193)
Lansing	3750' (-1543)	Misener Sand	4402'	(-2195)
Base Kansas City	4062' (-1855)	Viola	4435'	(-2228)
		Schlumberger T. D.	4503'	(-2296)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and fore-going is a true and correct copy of the log of the EDWARDS #1, NE NE NE, Section 26-20-19, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY: Gordon L. Koelling
Gordon L. Koelling, Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 29th day of July, 1955.

Leah Faye Hefke
Leah Faye Hefke, Notary Public

My commission expires June 16, 1959

PLUGGING
 FILE SEC 26 T 20 R 19W
 BOOK PAGE 138 LINE 17

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 26 1955
 CONSERVATION DIVISION
 Wichita, Kansas