


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 1 Twp. 20S Rge. 20W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

C-SW NE
Lease Owner Mr. L.V. (Stan) Bell d/b/a Bell Oil Company
Lease Name Snodgrass Well No. 1
Office Address 360 N. 135th W., Wichita, Kansas 67235
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plan

Dry Hole
Date Well completed September 17, 1978
Application for plugging filed Verbal Application 1978
Application for plugging approved Verbal Approval 1978
Plugging commenced September 17, 1978
Plugging completed September 17, 1978
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,262'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	513'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,262 ft. (rotary total depth) to 550 ft. Set plug at 550 ft. and cemented with 70 sacks cement. Filled hole with heavy rotary mud from 550 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 2 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing, Inc.
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~EMPLOYEE~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September, 1978



Elsie Willison
Notary Public.

My commission expires July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1978

CONSERVATION DIVISION
Wichita, Kansas

21-78

KANSAS DRILLERS LOG

COMPANY Mr. L.V. (Stan) Bell
d/b/a Bell Oil Company
FARM Snodgrass NO. 1

SEC. 1 T. 20S R. 20W
LOC. C-SW NE

ROTARY TOTAL DEPTH 4,262'
COMM. September 9, 1978 COMP. September 17, 1978
CONTRACTOR H-30, Inc.
ISSUED September 20, 1978

COUNTY Pawnee

CASING

10 3/4"
8 5/8" Set at 513' cemented w/300 sxs cement
5 1/2"
4 1/2"

ELEVATION 2,252 H.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	520'
Shale and Red Bed	840'
Sand	1,000'
Sand, Shale and Red Bed	1,415'
Anhydrite	1,448'
Shale	2,140'
Shale and Lime	2,315'
Lime and Shale	2,700'
Lime	3,200'
Lime and Shale	3,330'
Lime	4,262'
Rotary Total Depth	4,262'

I hereby certify the above and foregoing to be
a true and correct log of the above described
well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 20th day of
September, 1978.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1978

CONSERVATION DIVISION
Wichita, Kansas