

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 1 Twp. 20S Rge. 20W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NW SE SW


Lease Owner Antares Oil Corporation
Lease Name Carr #1 Well No. 1
Office Address 1546 Cole Blvd, Suite 220, Golden, Colo. 80401
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed September 28, 1980
Application for plugging filed September 28, 1980
Application for plugging approved September 28, 1980
Plugging commenced 12:30 PM September 28, 1980
Plugging completed 2:00 PM September 28, 1980
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4400'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	477'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug-set.

Filled hole with heavy mud.
Plugged with 70 sacks at 730';
25 sacks at 360'; 1/2 sack hulls and
plug at 40' and 10 sacks to surface. Used
50/50 Pozmix with 4% gel. 2 sacks in mousehole; 3 sacks in rathole.

(If additional description is necessary, use BACK of this form.)
Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas
NOV - 5 1980

STATE OF KANSAS COUNTY OF RICE
F. A. Wuellner (employee of owner) or Secretary or operator

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 19 80.

CHARLES M. HALL
Rice County, Ks.
My Appt. Exp. Jan. 31, 1982

Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires _____



October 26, 1980

State Corporation Commission
Conservation Division
245 North Water
Wichita, Kansas 67202

Re: Invoice #3350-W - Plugging Assessment
for Frick #1 - NW SE SW, Sec. 1-20S-20W
Pawnee County, Kansas
Our Prospect #327

Gentlemen:

Enclosed please find copy of well plugging application, well log and well plugging record on the Carr #1 (API #15-145-20,710). The drilling application with this API# on it was filed for the Frick #1 and the name was changed to the Carr #1. A revised drilling permit was to be filed but was not done.

If you need more information, please call.

Sincerely,

Barbara A. Pensiero
Production Department

bp/s

Enclosures

RECEIVED
STATE CORPORATION COMMISSION
NOV - 5 1980
CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - CARR #1
Located: NW SE SW, Section 1-20S-20W, Pawnee County, Kansas

OWNER: Antares Oil Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 21, 1980
COMPLETED: September 28, 1980

TOTAL DEPTH: 4400'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 280 Shale	Ran 12 joints 8 5/8" casing, 464.64' pipe set at 477' K.B. Cemented with 275 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 10:15 PM, 9-21-80, by Allied.
280 - 480 Red Bed	
480 - 1435 Shale	
1435 - 1466 Anhydrite	
1466 - 2153 Shale	
2153 - 4400 Lime and Shale	Plugged.

Deviation Surveys: 3/4° at 2153'
1 1/2° at 4305'

RECEIVED
STATE CORPORATION COMMISSION

NOV - 5 1980

CONSERVATION DIVISION
Wichita, Kansas