

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 22 Twp. 20 Rge. 19 (E) (W) X

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNWSW" or footage from lines. NE SE
Lease Owner Mull Drilling Company, Inc.
Lease Name Holman Well No. 1
Office Address 1625 Wichita Plaza Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 2-12-68 19____
Application for plugging approved 2-13-68 19____
Plugging commenced 2-15-68 19____
Plugging completed 2-24-68 19____

Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4315 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	STATE CORN.	FROM	TO	SIZE	PUT IN	PULLED OUT
					8 5/8	364	None
					4 1/2	None	2394

STATE CORN. FEE
CONSERVATION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1968
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Rigged up.

Cleaned out cellar. Sanded to 4200'. Dumped 4 sacks of cement. Working pipe.

Shot pipe at 3650'. Working pipe.

Working pipe. Shot pipe at 3500' - 3400' - 3300' - 3200' - 3100' and 3020'.

Working pipe. Shot pipe at 2800' - 2700' - 2600' - 2500' and 2400'. Pulling pipe.

Pulling pipe. Cleaned and doped collar threads.

Squeezed well with 16 sacks of mud and 5 sacks of hull and 120 sacks of cement by Globe Cementing Company.

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27 day of February, 19 68

My commission expires May 27, 1969
G. L. [Signature] Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company. MULL DRILLING CO.
Farm. Holman No. 1

SEC. 32 T. 20 R. 19W
C NE SE

Total Depth. 4315'
Comm. 5-29-61 Comp. 6-10-61
Shot or Treated.
Contractor. Red Tiger Drlg. Co.
Issued. 9-16-61

County Pawnee
KANSAS



Elevation. 2228' DR

Production. 50 BOPD

CASING:

8 5/8" 364' cem w/225 sx.
4 1/2" 4314' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface clay & shale	100
shale	140
shale & sand	200
shale	365
shale & shells	795
sand	925
red bed, shale	1348
Anhydrite	1378
shale & shells	1875
shale	2185
shale & lime	2465
lime	2555
lime & shale	3845
lime	4205
lime, shale, sand	4243
Coring	4290
lime & shale	4305
chat	4310
chat	4315
Total Depth	

TOPS: SCOUT

Anhydrite	348
Towhee	3708
Douglas	3722
Jansing	3736
Base Kansas City	4048
Cherokee	4194
Mississippi	4299

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1968

CONSERVATION DIVISION
Wichita, Kansas