


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Pawnee County, Sec. 22 Twp. 20S Rge. 19 (E) (W)X  
Location as "NE/CNW&SW" or footage from lines C NE NE  
Lease Owner Mull Drilling Company, Inc.  
Lease Name Holman Well No. 3  
Office Address 1625 Wichita Plaza Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 6-9-67 19  
Application for plugging approved 6-10-67 19  
Plugging commenced 6-23-67 19  
Plugging completed 7-5-67 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation Depth to top Bottom Total Depth of Well 4326 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	372	None
				7 1/2	None	3691

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 17 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed from feet to feet for each plug set.

Moved in. Cleaned out cellar.

Sanded to 1200'. Dumped 1/2 sacks of cement. Working pipe. Shot pipe at 3790' and 3670'.

Working pipe.

Pulling pipe.

Bailing hole down. Pushed plug to 350' rock bridge. Dumped 6 sacks of cement.

Bailed hole dry. Dumped 19 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7 day of July, 19 67

My commission expires May 27, 1969

Notary Public.

DRILLERS LOG

Holman No. 3

CASING RECORD: COMPANY: Mull Drilling Company DESCRIPTION: C NE NE  
 8 5/8" @ 372.71 CONTRACTOR: Red Tiger Drilling Co. 22-208-19W  
 w/200 ex cement COMMENCED: November 20, 1961 Pawnee Co.,  
 Kansas  
 4 1/2" @ 4326.65 COMPLETED: November 20, 1961 ELEVATION: 2224 KB  
 w/125 ex cement  
 TOTAL DEPTH: 4326'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Clay	0	100	
Shale & Shells	100	370	
Shale	370	525	
Shale & Hard Sand	525	560	
Shale	560	765	
Sand	765	980	
Shale & Shells	980	1335	
Anhydrite	1335	1385	
Shale & Shells	1385	2150	
Lime & Shale	2150	2425	
Lime	2425	2535	
Lime & Shale	2535	2630	
Lime	2630	2750	
Lime & Shale	2750	3075	
Lime	3075	3330	
Lime & Shale	3330	3505	
Lime	3505	4326	

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 12 1967  
 CORPORATION DIVISION  
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle  
 George A. Angle

Subscribed and sworn to before me this 4th day of December, 1961.

Wesley Head  
 Notary Public

My Commission Expires:

11-17-63