


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Pawnee County, Sec. 13 Twp. 20 Rge. 19 ~~(E)~~ ^{XX} (W)
Location as "NE/CNW/SW" or footage from lines C E/2 SE SW
Lease Owner The Carl Todd Drilling Company
Lease Name Ideker "A" Well No. 1
Office Address 404 KFH Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-6 19 54
Application for plugging filed 10-6 19 54
Application for plugging approved 10-6 19 54
Plugging commenced 10-6 19 54
Plugging completed 10-6 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4260 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
LOG ATTACHED						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 240', cemented plug with 20 sacks, filled hole to 35', cemented plug with 10 sacks to bottom of cellar

STATE CORPORATION COMMISSION

OCT 12 1954

10-12-54

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Carl Todd Drilling Company
Address 404 KFH Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Carl Todd (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Todd
404 KFH Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of October, 19 54

My commission expires December 14, 1957

Martha Long
Notary Public.



THE CARL TODD DRILLING COMPANY
404 KFH Building
Wichita, Kansas

#1 Ideker "A"
C E/2 SE SW Sec. 13-20-19W
Pawnee County, Kansas

COMMENCED: September 23, 1954
COMPLETED: October 6, 1954

CASING RECORD

ELEVATION: 2176 Kelly Bushing

Set 8-5/8" surface casing at 240'
cemented with 150 sacks

0 - 240	Surface clay and shale
240 - 275	Shale
275 - 320	Sand
320 - 400	Shale and shells
400 - 550	Shale
550 - 690	Red Bed
690 - 860	Sand
860 - 950	Shale
950 - 1050	Red Bed, Shale and sand
1050 - 1285	Red Bed
1285 - 1315	Anhydrite
1315 - 1475	Shale
1475 - 1760	Shale
1760 - 2090	Shale and shells
2090 - 2240	Shale and shells
2240 - 2385	Lime and shale
2385 - 2495	Lime and shale
2495 - 2585	Shale and shells
2585 - 2655	Lime, shale & sand
2655 - 2765	Shale and lime
2765 - 2880	Shale and shells
2880 - 2955	Lime and shale
2955 - 3080	Shale and lime
3080 - 3185	Shale and lime
3185 - 3245	Lime and shale
3245 - 3280	Shale and lime
3280 - 3325	Lime and shale
3325 - 3380	Lime and shale
3380 - 3450	Lime
3450 - 3540	Lime and shale
3540 - 3580	Lime and shale
3580 - 3685	Lime and shale
3685 - 3745	Lime
3745 - 3815	Lime
3815 - 3918	Lime
3918 - 4050	Lime
4050 - 4103	Lime
4103 - 4131	Lime, shale & Chert
4131 - 4164	Cong.
4164 - 4202	Lime
4202 - 4250	Lime
4250 - 4260	Lime
4260	Rotary Total Depth

TOPS

Heebner	3601
Toronto	3622
Lansing	3649
Base K. C.	3966
Conglomerate	4095
Arbuckle	4152

Drill Stem Test 4085 - 4103
Weak blow for 10 minutes, open 45
minutes, recovered 30' mud, rare
specks of oil. Initial & Final Flow
zero. BHP 260 in 15 minutes.

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1954

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log, to the
best of my knowledge and belief.

THE CARL TODD DRILLING COMPANY

By:

Carl Todd

PLUGGING
FILE SEC 13-20-R-19W
BOOK PAGE 69 LINE 32