

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

X			
X			

Locate well correctly on above
Section Plat

Pawnee County, Sec 18 Twp 20 Rgc. 19 (E) (W)
 Location as "NE/CNW/SE/SW" or footage from lines NW SW NW
 Lease Owner National Cooperative Refinery Assn.
 Lessor Name Eckert Well No. 2
 Office Address Box 908 McPherson, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) _____
 Date well completed _____ 19____
 Application for plugging filed 7/74 _____ 19____
 Application for plugging approved 7/74 _____ 19____
 Plugging commenced 7/22/74 _____ 19____
 Plugging completed 7/29/74 _____ 19____
 Reason for abandonment of well or producing formation _____

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1974

If a producing well is abandoned, date of last production _____
 Was permission obtained from the Conservation Division or its agent in _____
 _____ was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	457	None
				7"	4323	2200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

7/22/74 Plug off Bottom - Dumped sand to 4100,
Mixed and dumped 6 sx. cement.

7/29/74 Plug off Top - Allied Cementing Co. Mixed and
pumped down 10 3/4 " surface casing.
25 sx. gel. - Plug - 60 sx. cement - 10 sx.
gel. and 25 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1974
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Russ Casing Pulling Inc.
 Address Box 1082 Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON ss.
Earl Baker Jr. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct. So help me God.

(Signature) Earl Baker Jr.
Box 6, Great Bend, Kansas 67530
 (Address)

Subscribed and sworn to before me this 21st day of August 1974



Patricia Bradley
 Patricia Bradley Notary Public.

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-145:19067.0000

COPY

Company- NATIONAL COOPERATIVE REFINERY ASSOCIATION
 Firm- Eckert No. 2


SEC. 18

T. 20 R. 19W
 NW SW NW

Total Depth. 4330
 Comm. 1-2-55 Comp. 1-20-55
 Shot or Treated.
 Contractor. Sterling Drlg Co.
 Issued. 3-26-55

County

Pawnee
 KANSAS



10 3/4" CASING:
 7" 457' cem w/300 sx
 4323' cem w/100 sx

Elevation. 2233 KB

Production. 120 Bbbls

Figure indicates Bottom of Formations

sand, shale	400
shale	470
red bed, shale	820
sand	950
red bed, shale	1350
anhydrite	1385
red bed, shale	1440
shale, shells	2075
shale, limestone	2185
limestone	2550
limestone, shale	2635
limestone	2770
limestone, shale	3500
limestone	4135
limestone, shale	4190
limestone, shale, sand	4206
sand	4215
limestone, sand	4220
shale, sand	4232
limestone, shale	4295
shale	4313
limestone	4330
Total Depth	

Tops: Scout	
Anhydrite	1350
Heebner	3684
Kansas City	3731
Congl. sand	4201
Mississippi	4313

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 18 1954
 CONSERVATION DIVISION
 Wichita, Kansas