


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Pawnee County, Sec. 7 Twp. 20S Rge. 20W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C S W NE  
Lease Owner Pickrell Drilling Company  
Lease Name Batchman "A" Well No. 2  
Office Address 705 4th National Bank Bldg.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 28, 1968 19  
Application for plugging filed December 28, 1968 19  
Application for plugging approved December 28, 1968 19  
Plugging commenced December 28, 1968 19  
Plugging completed December 28, 1968 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4379 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	269'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 600'. Set plug. Cemented with  
70 sacks cement. Heavy mud to 240'. Set plug.  
Cemented with 20 sacks. Heavy mud to 40'. Set  
plug. Cemented with 10 sacks. Plugged rat hole with  
2 sacks cement.


RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 4th National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 4th National Bank Bldg., Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 3rd day of January, 19 69



My commission expires May 10, 1970

L. M. Whiting  
Notary Public.

**ROTARY DRILLING LOG**

15.145.20094.0000

COMPANY: PICKRELL DRILLING COMPANY  
705 4th National Bank Bldg, Wichita, Kansas  
LOCATION: Batchman "A" No. 2, C SW NE Sec. 7-20S-20W  
Pawnee County, Kansas

Rotary Drilling Commenced 12-17-68  
Rotary Drilling Completed 12-28-68

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
**Wichita, Kansas**

CASING RECORD: Ran 14 jts. used 28# 8 5/8" casing set at 269' KB, cemented with 160 sacks. Completed 8:15 PM. Circulated. No oil string run. D & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

269	Shale & Shells	<u>C. F. S.</u>
570	Shale	4379
850	Shale & Shells	
1070	Sand	
1397	Shale & Shells	
1435	Anhydrite	
1925	Shale & Shells	
2200	Shale & Lime	
2320	Lime & Shale	<u>Slope Tests</u>
2700	Lime	
2885	Lime & Shale	2000
3800	Shale & Lime	2500
4305	Lime	3000
4365	Lime & Chert	3500
4379	Mississippian RTD	4000

S. L. M

Board 4191.42  
Strap 4189.07  
No Corr. 2.35

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1969  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.


PICKRELL DRILLING COMPANY  
By [Signature]  
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

3rd day of January, 1969, before me the undersigned, a Notary Public, in and for

aforesaid, personally appeared C. W. Sebitts, to me known to be the Attorney-in-Fact who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



My Commission Expires: May 10, 1970

[Signature]  
Notary Public  
E. M. Whiting