

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (03/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-145-20,607 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR: NORTHSTAR INVESTMENTS, INC. KCC LICENSE #30,601 ^{12/96}
ADDRESS: 13735 PINNACLE CITY: WICHITA STATE: KS
ZIP CODE: 67230-1545 CONTACT PHONE # (316) 733-8997

RECEIVED
KANSAS CORPORATION COMMISSION

LEASE: BAYER WELL# 1 SEC. 7-T.20S-R.20W

SPOT LOCATION: W/2-SW-SE, COUNTY: PAWNEE

NOV 07 1996

660 FEET FROM THE SOUTH LINE OF SECTION (NOT Lease Line)
2310 FEET FROM THE EAST LINE OF SECTION (NOT Lease Line)

11-7-96
CONSERVATION DIVISION
WICHITA, KS

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE: N/A SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE: 8 5/8THS SET AT 257' CEMENTED WITH ? SACKS
PRODUCTION CASING SIZE: 5 1/2" SET AT 4,414", CEMENTED WITH 75 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4,376 TO 4,380

ELEVATION: 2,236 KB T.D.: 4,420, PBD N/A ANHYDRITE DEPTH: 1430
CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING: SAND OFF BOTTOM OF HOLE TO 4,360, SHOOT OFF CASING (APPROX. 3,800') SPOT 25 SXS CEMENT, PULL CASING TO 1,350 AND SPOT 50 SXS CEMENT, PULL CASING TO 90 FEET AND SPOT 25 SXS CEMENT. 4 SXS CEMENT DOWN BACKSIDE.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES

IS ACO-1 FILED? YES _____ If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A.55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DEAN BRITTING _____ PHONE# (316)733-8997

ADDRESS: 13735 PINNACLE _____ City/State: WICHITA, KS 67230

PLUGGING CONTRACTOR: QUALITY WELL SERVICE _____ KCC LICENSE # 31925 ^{8/97}
(contractor's)

ADDRESS: 249 EAST BETH DRIVE, STERLING, KS.67579 PHONE # (316)278-2476

PROPOSED DATE AND HOUR OF PLUGGING: ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: NOVEMBER 5, 1996 / AUTHORIZED OPERATOR/AGENT: Dean Britting
(signature)

15.145.20607.0000

FIELD PACKET

Electra Inc.

SEC. 7 TWP. 20S RGE. 20W

RADIATION ACCURLOG

COPY

COMPANY TOM CAT LTD.
15-145-20607
 WELL # 1 BAYER
 FIELD PAWNEE
 COUNTY PAWNEE STATE KANSAS

Location W/2 SW SE Other Services:
 Sec. 7 Twp. 20S Rge. 20W

Permanent Datum: Ground Level Elev. 2231 Elev.: K.B. 2236
 Log Measured From K.B. Five Ft. Above Perm. Datum D.F. 2233
 Drilling Measured From Kelly Bushing G.L. 2231

Date	10-31-79				
Run No.	ONE				
Depth-Driller	4420				
Depth-Logger	4404				
Btm. Log Inter.	4404				
Top Log Inter.	0				
Casing-Driller	8 5/8 @ 272				
Casing-Logger					
Bit Size	7 7/8				
Type Fluid in Hole	Starch Mud				
Dens.	Visc.	10.0	63		
pH	Fluid Loss	6.8	9.2 ml	ml	ml
Source of Sample	Flowline				
R ₁ @ Meas. Temp.	.2 @ 77 °F	@ °F	@ °F	@ °F	@ °F
R ₂ @ Meas. Temp.	.16 @ 77 °F	@ °F	@ °F	@ °F	@ °F
R ₃ @ Meas. Temp.	@ °F	@ °F	@ °F	@ °F	@ °F
Source: R ₁ R ₂	Charts				
R ₁ @ BHT	.09 @ 115 °F	@ °F	@ °F	@ °F	@ °F
Time Since Circ.	None				
Max. Rec. Temp.	115 °F	°F	°F	°F	°F
Equip. Location	138 Gt. Bend, Ks.				
Recorded By	D. Erickson				
Witnessed By	Mr. Kathol				

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 07 1996

CONSERVATION DIVISION
WICHITA, KS



15.145.20607.0000

Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

November 8, 1996

Northstar Investments Inc
13735 Pinnacle
Wichita KS 67230-1545

Bayer #1
API 15-145-20,607
660 FSL 2310 FEL
Sec. 07-20S-20W
Pawnee County

Dear Dean Britting,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760