

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-145-21,297.0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Kodiak Petroleum, Inc. OPERATORS LICENSE NO. 9971 10/20

ADDRESS 44 Inverness Dr. East, Bldg. D, Englewood, CO 80112 PHONE # (303) 790-7550

LEASE (FARM) Ellis WELL NO. 9-8 WELL LOCATION NW/SE/NE COUNTY Pawnee

SEC. 9 TWP. 20S RGE. 19 (~~EXX~~(W) TOTAL DEPTH 2500' PLUG BACK TD 2439'

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 464' CEMENTED WITH 225 SACKS

CASING SIZE 4 1/2" SET AT 2499' CEMENTED WITH 105 SACKS

PERFORATED AT 2325'-2331', 2344'-2349', 2371'-2377', 1SPF

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Sand to 2275', 4 sx cmt, Shut off casing

@ 1864' Pull casing, 300 lbs. Hulls, 10 sx of gel, 50 sx of 60/40 Pozmix w/ 60% gel,

10 sx of gel, 100 lbs. Hulls, 150 sx of 60/40 Pozmix w/ 60% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes * IS ACO-1 FILED? Yes
(If not, explain)*Original and well log sent to K.C.C., Wichita

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Approximately 10 A.M., December 21, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Mr. Harvey E. Moore

PHONE # (913) 628-6040

ADDRESS 2900 Willow St., Hays, Kansas 67601

PLUGGING CONTRACTOR Allied Cement Co. LICENSE NO. ?

ADDRESS P O Box 31, Russell, Kansas 67665 PHONE # (913) 483-2627

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]

(Operator or Agent)
Kent A. Johnson

DATE: December 19, 1989

①

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1989
12-22-89
CONSERVATION DIVISION
Wichita, Kansas

15-145.21297.0000

K.C.C.

FINAL PRINT

Schlumberger

CEMENT BOND LOG / VARIABLE DENSITY

COUNTY PAWNEE	FIELD ORO	LOCATION NW SE NE	WELL ELLIS #9-8	COMPANY KODIAK PETROLEUM INCORPORATED	COMPANY KODIAK PETROLEUM INCORPORATED					
					WELL ELLIS #9-8					
COUNTY PAWNEE	FIELD ORO	LOCATION NW SE NE	WELL ELLIS #9-8	COMPANY KODIAK PETROLEUM INCORPORATED	FIELD ORO					
					COUNTY PAWNEE		STATE KANSAS			
COUNTY PAWNEE	FIELD ORO	LOCATION NW SE NE	WELL ELLIS #9-8	COMPANY KODIAK PETROLEUM INCORPORATED	LOCATION 3630' FSL & 890' FEL				Other Services: PERF	
					API SERIAL NO. 15-145-21,297	SECT. 9	TWP. 20S	RANGE 19W		
Permanent Datum					GL	Elev.	2264.0 F	Elev.: K.B.2269.0 F		
Log Measured From					KB	5.0 F	above Perm. Datum		D.F.2267.5 F	
Drilling Measured From					KB				G.L.2264.0 F	
Date	25-AUG-1989				RECEIVED STATE CORPORATION COMMISSION DEC 22 1989 CONSERVATION DIVISION Wichita, Kansas					
Run No.	ONE									
Depth Driller	2498.0 F									
Depth Logger (Schl.)	2439.0 F									
Btm. Log Interval	2430.0 F									
Top Log Interval	1700.0 F									
Type Fluid In Hole	KCL WATER									
Salinity NaCl										
Density	8.00 LB/G									
Fluid Level	5.0 F									
Max. Rec. Temp.	98.0 DEGF									
Deviation										
Logger on Bottom					0900					
Equip.	Location		8363		GREAT BEND					
Recorded By					INGRAHAM					
Witnessed By					MOORE					
BOREHOLE RECORD										
Bit Size	7 7/8"									
Depth	2500.0 F									
CASING & TUBING RECORD										
Size	8 5/8"		4 1/2"							
Weight	24.0000 LB/F		9.5000 LB/F							
Casing Top-Driller										
Casing Top-Logger										
Casing Shoe-Driller					463.0 F		2400.0 F			
Casing Shoe-Logger					463.0 F					



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
MAR 28 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

December 28, 1989
NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Kodiak Petroleum, Inc.
44 Inverness Dr. East, Bldg D
Englewood, Co 80112

Ellis 9-8
NW SE NE
Sec. 09-20-19W
Pawnee County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760