

State of Kansas



15.145.38094.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. WALKER of TRAINS-WILLIAMSON has this
date requested permission to plug the following described well:

Mr. WALKER guarantees payment of the plugging fee.

Operator's full Name: TRAINS-WILLIAMSON OIL CO.

Complete Address: 1425 WICHITA PLAZA WICHITA, KANS.

Lease Name: DRAKE Well No. 1

Location: C-SE-NW Sec. 17 Twp. 20 Rge. 19 (E)(W) X

County PAWNEE Total Depth 4362 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. WALKER was instructed to plug the well as follows:

Jet pits circulate hole with heavy mud, set cementing plug at 600 ft.,
and displace 30 sac cement thru drill pipe, heavy mud to 380 ft., set
cementing plug and displace 20 sac cement thru drill pipe, heavy mud
to 40 ft., set cementing plug, 1/2 sac hulls and 10 sac cement, cementing
to base of collar. Plug rat hole with two sac cement.

Very truly yours,

Geo Massy
Conservation Division Agent