

State of Kansas



15-145-20326-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Michael of Search Drlg. has this
date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: Tomlinson Oil Co.

Complete Address: Suite 1030, 200 W. Douglas Wichita, Ks.

Lease Name: Boyd Well No. 1

Location: SW NE SE Sec. 25 Twp. 20 Rge. (E)(W) 19

County: Pawnee Total Depth 4030' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Michael was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 550' and displace
50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey
Conservation Division Agent