



15-145-20917-0000

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

8 December 1981

#### VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-145-20,917

Dear Sir:

Mr. Leroy Borron of Blue Goose Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Plano Petroleum Co.

Complete Address: 1130 East Plano Park Way #100 Box 1386 Plano Texas 75074

Lease Name: Snodgrass Well No. 1

Location: SW-SW-SE 1/4 Sec. 1 Twp. 20 Rge. 20W (E) (W)

County: Pownee Total Depth: 4410

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Borron was instructed to plug the well as follows:

*There is 5-34' of 8 3/8" surface casing cement circulated with 275 Sbk of cement, 2 3/4 Jell 3% C.C. The anhydrite was at 1470' and the Dakota at 1200'. 1st plug with hole full of heavy mud was at 1425' with 70 Sbk of cement. 2nd plug push rubber plug to 510' and pumped 35 Sbk of cement on top of it. 3rd plug 40' to 5' on solid bridge with 10 Sbk of cement. They pumped 5 Sbk of cement in each the rat hole & the mouse hole. Plugging accomplished by Allied Cement.*

Very truly yours,

Paul Luthi  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

DEC 1 1 1981

CONSERVATION DIVISION  
Wichita, Kansas

12-11-81