



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Baker of NCRA has this

date requested permission to plug the following described well:

Mr. Baker guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Association

Complete Address: Box 6^c Great Bend, Kansas 67530

Lease Name: Marlett Well No. I

Location: NE NE Sec. 12 Twp. 20 Rge. (E)(W) 19

County: Pawnee Total Depth 4255' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Baker was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
50 sk cmt thru drill pipe. Heavy mud to 300' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Rec L. Marshall
Conservation Division Agent