



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Roy Lindsey of Merble Ndg Co has this date requested permission to plug the following described well:

Operator's Full Name: Halliburton Oil Producing Co.

Complete Address: 2915 Claason Blvd., Oklahoma City, Ok.

Lease Name: Hanken Well No. #1

Location: C-SE-NE Sec. 19 Twp. 20 Rge. 19 (E) (W)

County: Pawnee Total Depth: 4241 FE

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Lindsey was instructed to plug the well as follows:

8 5/8" 420 EF SP. CUM w/ 275<sup>SE</sup> 60/40 Pozmix-2% Gel. 3% CaCl.

Order 115<sup>SE</sup> 50/50 Pozmix 6% Gel. & 8 5/8" Plug.

Spot with Drill Stem - with Heavy Mud Between all Plugs

1<sup>st</sup> Plug @ 680 FE w/ 65<sup>SE</sup> emt.

2<sup>nd</sup> Plug @ 240 EF w/ 30<sup>SE</sup> emt.

3<sup>rd</sup> Plug. Solid Bridge @ 40 EF w/ 10<sup>SE</sup> emt.

5<sup>th</sup> In Cat Hole.

5<sup>th</sup> In Mouse Hole.

Very truly yours, By Halliburton Co.

Marion Schmidt  
Conservation Division Agent