



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 23 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Oller of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Vincent F. Hiebsch

Complete Address: 625 Union Center Wichita, Ks.

Lease Name: Pfenninger Well No. 1

Location: 440' SNL 880' WEL of SW/4 Sec. 8 Twp. 20 Rge. 19 (E)(W) XX

County: Pawnee Total Depth 4179' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Oller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace

70 sc cement thru drill pipe. Heavy mud to 330' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2' sc cement.

Very truly yours,

Geo. F. Mansuet
 Conservation Division Agent