

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 2 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

December 17, 1962

Dear Sir:

Mr. Albert Schiffner of National Coop. Refinery ^{Assoc.} has this

date requested permission to plug the following described well:

Mr. Albert Schiffner guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Assoc.

Complete Address: 305 Rule Building Wichita, Kansas

Lease Name: Hagerman Well No. 10

Location: SW NE NW Sec. 10 Twp. 20 Rge. 19 (E) (W) X

County Pawnee Total Depth 4550 Oil Well X ^{abandoned}

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Albert Schiffner was instructed to plug the well as follows:

4548' of 5 1/2" oil string cemented with 125 sacks cement. Top

perforation 4179' . Sanded to 4170' and 5 sacks cement.

501' of 8 5/8" surface pipe circulated 250 sacks cement.

Hole filled to 300' with mud, 10' rock bridge and 20 sacks

cement. Hole filled to 40' with mud, 10' rock bridge and

10 sacks cement to base of

Very truly yours,

cellar.

Kenneth Gustus
 Conservation Division Agent