



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
CONSERVATION DIVISION  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dec. 15, 1962.

Dear Sir:

Mr. D. B. Pully of Forbes Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. D. B. Pully guarantees payment of the plugging fee.

Operator's full Name: National Coop Refining Assn.

Complete Address: Box 6 Great Bend, Kansas.

Lease Name: Hagerman # 6 Well No. #6

Location: NW-SW-SW Sec. 10 Twp. 20 Rge. 19 (E) (W)  X

County Pawnee County Total Depth 4252'  X Abandoned Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. D. B. Pully was instructed to plug the well as follows:

4253' of 5 1/2" long string cemented with 125 sacks cement.

Hole plugged back to 4234' Top perforation at 4178', sanded

4170', 5 sacks cement. 135' of 8 5/8" surface pipe circulated

with cement. Hole filled with mud to 120', 10' rock bridge

and 20 sacks cement. Hole filled to 40' with mud, 10' rock bridge & 10 sacks cement to base of cellar

Very truly yours,

*Harmon Gustafson*  
Conservation Division Agent