



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dec. 17, 1962.

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. D. B. Pully guarantees payment of the plugging fee.

Operator's full Name: National Coop Refining Assn.

Complete Address: _____

Lease Name: Hagerman # 7 Well No. #7

Location: SE-NW-SW Sec. 10 Twp. 20 Rge. 10 (E) (W) X

County Pawnee County Total Depth 4234' ^{Abandoned} Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. D. B. Pully was instructed to plug the well as follows:

4234' of 5 1/2" long string. Plugged to 4186'. Top perforation at 4161' sanded to 4150' & 5 sacks cement. 130' of 8 5/8" surface pipe circulated with cement. Hole filled to 120' with mud, 10' rock bridge & 20 sacks cement. Hole filled to 40' with mud; 10' rock bridge & 10 sacks cement to base of cellar.

Very truly yours,

Harman Justus
Conservation Division Agent