

State of Kansas



15-145.20559.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Dreiling of Gabbert-Jones Drlg. has this
date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Mahoney Drlg. Co., Inc.

Complete Address: 320 S. Boston Ste. 805 Tulsa, Ok.

Lease Name: Fleming Well No. 1

Location: C NE NW Sec. 32 Twp. 20 Rge. (E)(W) 17

County: Pawnee Total Depth 4040' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 420' thru drill
pipe. Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1973

Very truly yours,
CONSERVATION DIVISION
Wichita, Kansas

Red Massey
Conservation Division Agent