


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 8 Twp. 20S Rge. 20 SW
Location as "NE/CNW¹/SW¹" or footage from lines _____
NE SW SW
Lease Owner D N B Drilling, Inc.
Lease Name Norris Well No. 1
Office Address 515 R.H.Garvey Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above Section Plat

dry hole
Date Well completed 10-10-77 1977
Application for plugging filed 10-10 1977
Application for plugging approved 10-10 1977
Plugging commenced 10-10 1977
Plugging completed 10-10 1977
Reason for abandonment of well or producing formation
no commercial quantities of oil or gas encountered
If a producing well is abandoned, date of last production
____ 19____

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4400
Show depth and thickness of all water, oil and gas formations.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface hole	shale	surf	300'	8-5/8"	292	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 600', plug, 70 sx
Fluid to 300', plug, 20 sx
Fluid to 40', plug, 10 sx
3 sx in rat hole

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor D N B DRILLING, INC.
515 R. H. Garvey Building
Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ella Priess (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ella Priess
Suite 515, R.H.Garvey Bldg., Wichita, Ks.
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 11th day of October, 19 77

Dorothy L. Schmidt
Dorothy L. Schmidt Notary Public.

My commission expires April 30, 1979

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979

DRILLERS' LOG

D N B DRILLING, INC.
 No. 1 Norris
 NE SW SW Sec. 8-20S-20W
 Pawnee Co., Kansas

Commenced: 10-5-77
 Completed: 10-10-77

Surface Casing: 282' of 8-5/8"
 cmtd w/175 sx common, 2% gel, 3% cc
 10-5-77

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 300
Sand & Shale	300 - 620
Red Bed	620 - 815
Sand & Shale	815 - 1270
Shale	1270 - 1390
Andydrite	1390 - 1420
Shale w/Lime Streaks	1420 - 1975
Lime & Shale	1975 - 2520
Shale & Lime	2520 - 2780
Lime & Shale	2780 - 3070
Shale & Lime	3070 - 3615
Lime & Shale	3615 - 4230
Lime	4230 - 4360
Lime & Shale	4360 - 4400 RTD

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 19 1977
 CONSERVATION DIVISION
 Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 12th day of October 1977.

Dorothy L. Schmidt
 Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
 STATE NOTARY PUBLIC
 Sedgwick County, Kansas
 My Appt. Exp. April 30, 1979.