

15.145.20559.0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County. Sec. 32 Twp. 20 Rge. 17 N/W  
Location as "NE/CNW SW 1/4" or footage from lines  
C NE/4 NW/4

Lease Owner Mahoney Drilling Co., Inc.  
Lease Name Fleming Well No. 1

Office Address 320 So. Boston Suite 805 Tulsa, Ok. 74103  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole


Date Well completed 12-19 1978  
Application for plugging filed 12-19 1978  
Application for plugging approved 12-19 1978  
Plugging commenced 12-19 1978  
Plugging completed 12-19 1978

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production  
NA 19  

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation NA Depth to top    Bottom    Total Depth of Well 4040'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
NONE						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from    feet to  
   feet for each plug set.

- 50 sx 50/50 poz + 2% gel at 420'
- 25 sx 50/50 poz + 2% gel at 250'
- 10 sx 50/50 poz + 2% gel 40' solid bridge to surface
- 3 sx 50/50 poz + 2% gel in rat hole

RECEIVED  
STATE CORPORATION COMMISSION

JAN 23 1979

CONSERVATION DIVISION  
Pratt, Kansas

(If additional description is necessary, use BACK of this sheet.)  
Name of Plugging Contractor Haliburton

STATE OF Kansas COUNTY OF Pratt, ss.  
William K. Black (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) William K. Black  
PO box 510 Pratt, Ks. 67124  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of January, 1979

PHYLLIS GOSS  
State Notary Public  
Pratt County, Kansas 3-23-80

Phyllis Goss  
Notary Public.

My commission expires Appointment Expires: 3-23-80

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

Fleming #1  
C NE NW Sec 32-30S-17W  
Pawnee County Kansas

Commenced: 12-12-78

Completed: 12-19-78

OPERATOR: MAHONEY DRILLING CO.

Depth		Formation	Remarks	
From	to			
0	20	Top Soil-Post. Rock	Ran 9 jts of 20# 8 5/8" csg set @ 350' Cemented w/ 100 sks 50/50 Posmix + 100 sks Common 3% CC PD @ 1:00 p.m. 12-12-78	
20	40	Shale		
40	145	Post Rock		
145	351	Shale		
351	1070	Shale-Sand-Redbed		
1070	1188	Shale-Redbed		
1188	1212	Anhy		
1212	1735	Shale-Shells		
1735	2155	Shale-Lime		
2155	3735	Lime-Shale		
3735	4040	Lime		
	4040 - TD			DRY & ABANDONED

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above  
Drillers' Well Log is true and correct to the best of my knowledge and belief and  
according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
JAMES S. SUTTON II

Subscribed and sworn to before me this 22nd day of December, 1978.

*Elizabeth J. Edwards*  
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.



RECEIVED  
STATE CORPORATION COMMISSION

JAN 23 1979

CONSERVATION DIVISION  
Wichita, Kansas