

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 32 Twp. 20S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines C NW NE
Lease Owner Appleton Oil Company (Not Inc.)
Lease Name FLEMING Well No. 1
Office Address 506 Beacon Building, Tulsa, Oklahoma 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 1, 19 68
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced October 1, 19 68
Plugging completed October 1, 19 68
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Leo Massey of Hays)

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4043 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	249'	8-5/8"	9/24/68	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from Total Depth to 500 Feet;
Plug and 50 sax Cement; Mud to 240 Feet;
Plug and 25 sax Cement; Mud to 40 Feet;
1/2 sax Hulls, Plug and 10 sax Cement to
Base of Cellar; 2 sax Cement in Rat Hole.
Job Completed @ 4 A.M. on 10/1/68.

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 - 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co. (Sun Cementing Co.)
Address 500 Bitting Bldg., Wichita, Kansas


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of October, 19 68

Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1970.



DRILLERS LOGFLEMING NO. 1

CASING RECORD:	OPERATOR: Appleton Oil Company	DESCRIPTION:
8-5/8" @ 249' w/150 sax cement	CONTRACTOR: Sage Drilling Co.	C NW NE Sec. 32-20S-17W Pawnee County, Kansas
TOTAL DEPTH: 4043'	COMMENCED: September 24, 1968	ELEVATION: 2118KB
	COMPLETED: October 1, 1968	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	251	
Shale	251	583	
Dakota Sand	583	729	
Shale & Red Bed	729	1172	
Anhydrite	1172	1199	
Red Bed & Shale	1199	1440	
Shale & Lime	1440	1900	
Lime & Shale	1900	2035	
Shale & Lime	2035	2275	
Lime & Shale	2275	2615	
Shale & Lime	2615	3160	
Lime & Shale	3160	3998	
Arbuckle dolomite	3998	4043	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 3rd day of October, 1968.

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 - 1968

CONSERVATION DIVISION
Wichita, Kansas

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.