

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 29 TWP. 20S RGE. 17 ~~FW~~
Location as in quarters or footage from lines:

1015' FSL - 785' FWL

Lease Owner Tenneco Oil Company
 Lease Name Hagerman Well No. 1-29 Okla. City
 Office Address 139 Ciudad Bldg., 3000 United Founders Blvd., Okla
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed August 18, 1981
 Application for plugging filed Verbal application
 Plugging commenced August 18, 1981
 Plugging completed August 18, 1981
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8	495'	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

- 60 sxs @ 700'
- 40 sxs @ 475'
- 10 sxs @ 40' w/solid wood bridge
- 5 sxs @ Rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Co.
Great Bend, KS 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Younger, Agent (~~agent~~ of owner) or (~~owner~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
251 N. Water, #10, Wichita, KS
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 24th day of August, 1981

[Signature]
Helen Pracht-Notary Public.

My Commission expires: June 4, 1985

RECEIVED
CORPORATION COMMISSION
AUG 28 1981
CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Tenneco Oil Company

SEC. 29 T. 20S R. 17W
LOC. 1015' NESEE- 785' FWL

FARM Hagerman NO. 1-29

COUNTY Pawnee

ROTARY TOTAL DEPTH 4100'
COMM. August 7, 1981 COMP. August 16, 1981
CONTRACTOR H-30 (Rig No. 2)
ISSUED August 24, 1981

CASING

10 3/4"
8 5/8" - set at 495' - cemented w/300 sxs cement ELEVATION 2162' K.B.
5 1/2"
4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay and Red Bed	340'
Shale	500'
Sand and Shale	1000'
Shale and Sand	1218'
Anhydrite	1248'
Shale	2070'
Lime and Shale	2595'
Shale	2750'
Lime and Shale	3115'
Shale	3235'
Shale and Lime	3415'
Lime and Shale	3645'
Lime	3848'
Lime and Shale	4015'
Lime	4100'
Lime and Shale	4100'
Rotary Total Depth	4100'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Gary Younger
Gary Younger

State of Kansas)
) ss
County of Sedgwick)

Subscribed and Sworn to before me, a Notary Public, in and for said county and state this 24th day of August, 1981.

Helen Pracht
Helen Pracht - Notary Public

My Commission Expires:
June 4, 1985

RECEIVED
AUG 28 1981
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas