


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County. Sec. 28 Twp. 20S Rge. 17W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C NW NE

Lease Owner Leeman Energy Corporation  
Lease Name Powell Well No. 1  
Office Address 50 Penn Place, Suite 1400, Okla. City, Ok. 73118  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed April 10 19 82  
Application for plugging filed April 10 19 82  
Application for plugging approved April 10 19 82  
Plugging commenced April 10 19 82  
Plugging completed April 10 19 82

Reason for abandonment of well or producing formation Dry Hole  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Metz  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3785'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	332'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

RECEIVED  
STATE CORPORATION COMMISSION

APR 27 1982

CONSERVATION DIVISION  
Wichita, Kansas

Plugged with 45 sx cement @ 3600',  
45 sx @ 2205', 60 sx @ 900', 30 sx @ 330',  
Bridge & 10 sx @ 40', 10 sx in rathole.  
(50/50 pozmix 4% gel & 3% c.c.)  
Halliburton

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & B Drilling, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Bill G. Lahar (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

*Bill G. Lahar*

515 Union Center, Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of April, 19 82

My commission expires



*Betty M. Abbott*  
Betty M. Abbott

Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

APR 27 1982

CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

April 19, 1982

#1 Powell  
C NW NE  
Sec. 28-20S-17W  
Pawnee Co., Kansas

OPERATOR: Leeman Energy Corporation  
CONTRACTOR: B & B Drilling, Inc.  
COMMENCED: April 1, 1982  
COMPLETED: April 10, 1982

8 5/8" @ 332' w/225 sx.

0	225	Surface clay & sand	
225	335	Shale & Shells	
335	445	Clay	
445	853	Sand & Redbed	
853	1149	Shale	
1149	1178	Anhydrite	
1178	2842	Shale	
2842	2983	Shale & Lime	
2983	3785	Lime	
3785		RTD	D & A

We certify that the above and foregoing is a true and correct copy of the log on the #1 Powell located in Pawnee County, Kansas.

B & B DRILLING, INC.

*Bill G. Laker*

Subscribed and sworn to before me this 19th day of April, 1982.



*Betty M. Abbott*  
Notary Public