


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pawnee County. Sec. 7 Twp. 20S Rge. 19 (#/ (W)
Location as "NE/CNW/SWK" or footage from lines SE NW SW
Lease Owner National Cooperative Refinery Association
Lease Name SCHNEIDER Well No. 3
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 9 19 56
Application for plugging filed February 9 19 56
Application for plugging approved February 10 19 56
Plugging commenced February 9 19 56
Plugging completed February 9 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Brundridge
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4348 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	505'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Mudded hole from 4348' to 480'. Set plug plus 35 sax of cement. Mudded hole to 45', set plug / 15 sax of cement. Filled on up to base of cellar. (Cemented by Globe Cementing)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor M.B. Armer
Address 710 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C.R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.R. Sears (C.R. SEARS)
305 Rule Building, Wichita, Kans
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of February, 19 56

My commission expires June 30, 1958

C. Orville May
C. ORVILLE MAY Notary Public.

PLUGGING
FILE SEC 7 T 20 R 19 W
BOOK PAGE 37 LINE 36

FEB
CONG. DIVISION
Wichita, Kansas
2-16-1956

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15.145.00946.0000

COMPANY **National Cooperative Refinery Association**

SEC. **7** T. **20** R. **19W**
 LOC. **C SE NW SW**

FARM **Schneider**

NO. **3**

TOTAL DEPTH **4348**


COUNTY **Pawnee**

COMM. **1/24/56**

COMP. **2/9/56**

KANSAS

SHOT OR TREATED



CONTRACTOR **Armer, Inc.**

ISSUED

CASING

20	10	
15	8	506'
12	6	
13	5	

ELEVATION **2252 X.B.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Soil, Shale & Shells	160
Shale & Shells	260
Sand	320
Shale & Shells	506
Shale	615
Red Bed & Sand	1030
Red Bed & Shells	1400
Anhydrite	1615
Shale, Red Bed & Shells	1660
Shale & Shells	2130
Shale & Lime	2240
Broken Lime	2355
Lime & Shale	3710
Lime	4235
Lime & Shale	4320
Shale & Chert	4348

FORMATION TOPS

HESENER	3725
LANSING	3772
BASE KANSAS CITY	4110
CHEROKEE SAND	4264
MISSISSIPPI	4337

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

By *L.P. Spradley*

STATE OF KANSAS |
 |
 COUNTY OF SEDGWICK | SS:

Subscribed and sworn to before me, a notary public, in and for said County and State this 13th day of February, 1956.

Rose Furey
 Notary Public

My Commission expires February 13, 1960.

RECEIVED
 STATE CORPORATION COMMISSION

FEB 18 1956

PLUGGING
 FILE SEC 7 T 20 R 19W
 BOOK PAGE 37 LINE 36